BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31099

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/02/2018-19, Date: 26.07.2018

Construction of drain and improvements of culverts at Balaji layout in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRAKASH RANGANATH (BRINDA CONSTRUCTIONS)	
				In Figures	In Words
1	126.9	Removing & Refixing stone slabs of drains and pointing in C.M.(1:3)	Cum	70.73	Rupees Seventy and Seventy Three Paise Only
2	465.3	KSRB 2-2.2:Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary Soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	Cum	76.32	Rupees Seventy Six and Thirty Two Paise Only
3	77.55	KSRB 4-1.3:Providing and layingi n position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications.	Cum	4529.62	Rupees Four Thousand Five Hundred Twenty Nine and Sixty Two Paise Only
4	148.05	KSRB 4.2.2:Providing andlaying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed -2008, machine mixed, concrete laid in layres not exceeding 15 cms, thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase,lintles, retaining walls, return walls, walls (any thickness) includng attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5699.87	Rupees Five Thousand Six Hundred Ninety Nine and Eighty Seven Paise Only
5	7.4	KSRB 4.9-1:Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wasstge shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	56405.72	Rupees Fifty Six Thousand Four Hundred Five and Seventy Two Paise Only
6	1128	KSRB 4-6.4:Providing and removing centering, shuttering, strutting proppoing etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters butresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	272.69	Rupees Two Hundred Seventy Two and Sixty Nine Paise Only
7	296.1	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 10cms thick	Sqm	725.0	Rupees Seven Hundred Twenty Five Only
8	2349	Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded	nos	32.57	Rupees Thirty Two and Fifty Seven Paise Only
9	942	5.29(b) Providing and fixing Pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with toop and bottom wideth 114 and 165 mm respectively 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, includng form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unoading lead and lift transportatin etc, complete.	nos	291.3	Rupees Two Hundred Ninety One and Thirty Paise Only

Signature of the contractor

29/12

Executive Engineer

29/12

	roved Qty.	Description	Unit	Approved Tender Rates of PRAKASH RANGANATH (BRINDA CONSTRUCTIONS)	
				In Figures	In Words
10	169.6	KSRRB 15-19.1:Providing and applying ready mix priming coat over concrete/ masonry/asbestos cement sheet/ plastered surfaces including preparing the surface after thoroughly cleaning of oil grease, dirt and other foreign matter, and sand preparing including cost of materials, labour complete as per specifications.	Sqm	24.2	Rupees Twenty Four and Twenty Paise Only
11	169.6	KSRRB 15-20.1:Providing and applying floor painting with redy mix paint in two coats (excluding priming coat) on new concret / asbestos cement sheet / plastered surfaces brushing to give an even shade qafter preparing the surface after throughly cleaning oil, diert, dust other foreign matter and sand preparing including cost of materials, labour, complete as per specifications.	Sqm	46.53	Rupees Forty Six and Fifty Three Paise Only
12	465.3	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	93.07	Rupees Ninety Three and Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

29/12

29/12